

Bauvorhaben: M52.D_P-K+S45+H_000E0MGGOMWHO90_A01

DACHGESCHOSS

BAD	2.495×3.355	=	8.37 m ²
	$0.50 \times 3.355 + 0.500$	=	0.84 m ²
	$0.50 \times 0.200 + 2.435$	=	0.24 m ²
	SUMME:		9.45 m²

DIELE	2.870×1.485	=	4.26 m ²
	0.995×1.242	=	1.24 m ²
	$0.50 \times 1.485 + 1.000$	=	0.74 m ²
	$0.00 \times 1.485 + 0.215$	=	0.00 m ²
	SUMME:		6.24 m²

ELTERN	2.870×3.855	=	11.06 m ²
	$0.50 \times 3.855 + 1.000$	=	1.93 m ²
	$0.00 \times 3.855 + 0.175$	=	0.00 m ²
	SUMME:		12.99 m²

KIND I	1.175×2.053	=	2.41 m ²
	5.043×2.245	=	11.32 m ²
	$0.50 \times 2.990 + 1.000$	=	1.50 m ²
	$0.00 \times 2.990 + 0.175$	=	0.00 m ²
	SUMME:		15.23 m²

KIND II	$0.5 \times (2.990 + 2.990) + 2.620$	=	7.83 m ²
	3.795×0.365	=	1.39 m ²
	1.438×3.420	=	4.92 m ²
	$0.50 \times 0.5 \times (2.990 + 2.990) + 1.000$	=	1.50 m ²
	$0.00 \times 0.5 \times (2.990 + 2.990) + 0.175$	=	0.00 m ²
	SUMME:		15.64 m²

ERMITTLUNG DER WOHNFLÄCHE
NACH FERTIGMASSEN DER
RÄUME (ROHBAU MINUS
PUTZSTARKE 1,5cm)

WOHNFLÄCHE:	59.55 m ²
- 0.00 % Putz =	59.55 m ²

gesamte Nettowohnraumfläche: 130.54 m²

BAUHERREN:

PLANVERFASSER:

Dipl.-Ing.
Carsten Grötjahn
MENSCHING GmbH
Chromstr. 12
30916 Isernhagen

ISERNHAGEN, DEN 28.11.2005

Tel.: 0511/7284-0
Fax.: 0511/7284333